

BRUHATH BANGALORE MAHANAGARA PALIKE,
DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division

Schedule - B

BBMP/2021-22/OW/WORK_INDENT50410

Name of Work: Maintaince of Park in ward No 12

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor Sri NAVEEN R (RNI ENTERPRISES)	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete with all lead and lift charges & as per direction of engineer incharge of work.	Cum	41.81	364.76	Rupees Three Hundred Sixty Four and Seventy Six Paise Only
2	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications with all lead and lift charges & as per direction of engineer incharge of work.	Cum	8.36	5332.41	Rupees Five Thousand Three Hundred Thirty Two and Forty One Paise Only

N-R

Signature of the Contractor,

Executive Engineer
Dasarahalli Division

3	Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete with all lead and lift charges & as per direction of engineer incharge of work.	Cum	31.36	4803.56	Rupees Four Thousand Eight Hundred Three and Fifty Six Paise Only
4	Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications with all lead and lift charges & as per direction of engineer incharge of work.	Cum	23.52	5730.61	Rupees Five Thousand Seven Hundred Thirty and Sixty One Paise Only
5	Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @ 0.43cum, with superplasticiser @3lts conforming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications with all lead and lift charges & as per direction of engineer incharge of work.	Cum	7.41	5568.61	Rupees Five Thousand Five Hundred Sixty Eight and Sixty One Paise Only
6	Providing flush pointing to square rubble, course or uncoursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications with all lead and lift charges & as per direction of engineer incharge of work.	Sqm	104.54	147.37	Rupees One Hundred Forty Seven and Thirty Seven Paise Only

NKR

bf

7	Supplying and fixing M.S. Rectangular poles made out of 2 equal angles of 65x65x6 mm welded together and fixed in CC (1:2:4) WITH 2 NOS 16mm dia M.S. hold fast rods each of length 25 cms. Including cost of all materials cutting, bending scaffolding wherever necessary, nicely finishing the welded joints with all lead lifts and as per the directions of the Engineerin - charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting (excluding cost of earthwork and concrete) with all lead and lift charges & as per direction of engineer incharge of work.	Rmtr	148.20	897.79	Rupees Eight Hundred Ninety Seven and Seventy Nine Paise Only
8	Providing and fixing M.S. Block pipe of 38mm dia, of heavy guage of 14 including removing the bends, cutting the pipe, and fixing pipe in between the two verticle poles (M.S. rectangular poles) and spot welding the chain link with M.S. block pipe including cost of all materials wastage in cutting, and scaffolding wherever necessary with all lead and lift as directed by the Engineer-in-charge of work etc., complete including two coats of approved quality paint over one coat of shop paint.with all lead and lift charges & as per direction of engineer incharge of work.	Rmt	232.30	426.43	Rupees Four Hundred Twenty Six and Forty Three Paise Only
9	Providing chain link fencing 50mm size of 8 guage properly stretched between rectangular poles and fixed with suitable bolts & nuts, the free ends shall be welded to the pole and block pipe at top and bottom as required including cost of all materials, labour, lead and lifts and as per the directions of the Engineer-in-charge of work including two coats of approved quality paint over one coat of shop paint with all lead and lift charges & as per direction of engineer incharge of work.	Sqm	243.92	747.29	Rupees Seven Hundred Forty Seven and Twenty Nine Paise Only



Signature of the Contractor,



Executive Engineer
Dasarahalli Division

10	Providing and applying painting in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications. with all lead and lift charges & as per direction of engineer incharge of work.	Sqm	278.76	94.06	Rupees Ninety Four and Six Paise Only
----	---	-----	--------	-------	---------------------------------------

NAR

Signature of the Contractor

kef

Executive Engineer,
Dasarahalli Division,